

ADDENDUM NO. 2
November 21, 2018

CITY OF MASCOUTAH
MAPLE PARK RESTROOM PROJECT

The Invitation for Bids for the Maple Park Restroom Project is hereby revised or clarified as described below.

- Dimensions given for the building (14' x 24') shall be interpreted as inside room dimensions sufficient for ADA compliance.
- Building gable ends above the block shall be sided with LP SmartSide, 8" lap siding, or equivalent.
- Eaves shall be 12" wide on all sides of the building.
- Concrete footings shall be per code, 6 bag mix (4,000 PSI).
- Utilities shall be extended out 5' from the building. City will extend water service from the south. City will determine if an existing sewer lateral exists and if none is found will extend a sewer lateral from the north. City will extend buried electric to the west side of the building.
- Interior walls between restrooms and mechanical room shall be smooth 8" concrete colored blocks supported by a block foundation wall on concrete footing same as exterior walls.
- Interior walls shall be smooth colored block and shall be sealed, not painted.
- Interior electric can be in conduit mounted on the surface of walls.
- Exterior water fountain shall be non-refrigerated.
- Skylight windows shall be minimum 24"x 24".

Submit signed copy of this addendum attached to Bidder's Proposal.

Acknowledged by: _____

Date: _____